



















SIGNING AND STRIPING NOTES

- \bigcirc EXISTING SIGN ON POLE TO REMAIN
- $race{2}$ REMOVE AND SALVAGE EXISTING SIGN
- $\ensuremath{\langle 5 \rangle}$ Existing sign to remain

2 INSTALL NEW SIGN

- 12 INSTALL 24" SOLID WHITE LINE
- (15) INSTALL BICYCLE LANE SYMBOL MARKING WITH GREEN BACKGROUND PER DETAIL ON SHEET 2
- 27 INSTALL 4" SOLID YELLOW LINE
- 28 INSTALL 8" SOLID YELLOW LINE
- (31) INSTALL YELLOW TUBULAR MARKER PER DETAIL ON SHEET 5 AT 20' SPACING
- (32) INSTALL 4" SOLID YELLOW 45" DIAGONAL HATCH AT 15' SPACING

GENERAL NOTES:

- 1. REMOVE AND REPLACE LANE LINES AS SHOWN ON ARAPAHOE STREET.
- 2. ALL TRAVEL LANE LINES SHALL BE INLAID.
- 3. CITY PARKING OPERATIONS WILL BE RESPONSIBLE FOR METER REPLACEMENT.
- 4. RTD TO REMOVE THEIR OWN SIGNS (TYP).
- 5. PROTECT EX. ROW TREES ADJACENT TO CONSTRUCTION ACTIVITIES, PARTICULARLY THOSE ADJACENT TO INSTALLATION OF ISLANDS, CURB CUTS, AND METER INSTALLATION.
- 6. CONTRACTOR SHALL COORDINATE TREE PROTECTION WITH FORESTRY STAFF PRIOR TO COMMENCEMENT OF CONSTRUCTION/DEMOLITION ACTIVITIES.
- 7. DIMENSIONS ARE FROM FLOW LINE TO CENTER OF STRIPE UNLESS OTHERWISE NOTED.
- 8. NEW SIGNS TO BE INSTALLED WITHIN 2' OF BEGINNING OR END OF PARKING STALLS.
- ALL LONG LINES SHALL BE INSTALLED IN EPOXY. DIAGONAL HATCHING, PARKING "T"'S, AND SYMBOLS SHALL BE INSTALLED IN PREFORMED THERMOPLASTIC TAPE.

REVISIONS DATE BY NO. Kimley»Horn 60% PRELIMINARY DESIGN 90% PRELIMINARY DESIGN 8/24/15 BWV KIMLEY-HORN AND ASSOCIATES, INC. 4582 SOUTH ULSTER STREET, SUITE 1500 DENVER, COLORADO 80237 (303) 228-2300



GRAPHIC SCALE IN FEET

ALTA PLANNING + DESIGN 1836 BLAKE STREET, SUITE 100 DENVER, COLORADO 80202 (720) 524-7831



UNDERGROUND SERVICE ALERT Call: TOLL FREE 811 / 1-800-227-2600 www.usanorth.org
TWO (2) WORKING DAYS BEFORE YOU DIG



Designed By: Checked By BWV 349003PM

CITY AND COUNTY OF DENVER ARAPAHOE STREET BIKEWAY SPEER BOULEVARD TO 24TH STREET SIGNING AND STRIPING PLAN

28 28